

[News](#) ▾[Business](#) ▾[Tech & Industry](#) ▾[Entertainment](#) ▾[Education](#) ▾[Health](#) ▾[Tourism](#) ▾[Sports](#)[Editor's column](#)[Magazine](#)[Home](#) > [General](#)

# Shri Ram Mandir in Ayodhya showcases Tata Consulting Engineers' Engineering Excellence

by NS — January 23, 2024 in General 0

**0** SHARES  
**19** VIEWS [Share on Facebook](#)[Share on Twitter](#)

Bengaluru : The consecration of the Shri Ram Mandir at the Shree Ram Janmbhoomi Teerth Kshetra complex in Ayodhya in the presence of the Hon'ble Prime Minister Shri Narendra Modi ji and other dignitaries is a historic moment. For Tata Consulting Engineers (TCE), it is a matter of pride to have contributed to the construction of the magnificent temple, setting new benchmarks in engineering excellence. TCE was appointed as the design review, engineering and project management consultant for the entire project to ensure that the amalgamation of ancient faith and modern science would be a place of worship that also signifies India's self-reliance and prowess in engineering.

The Shree Ram Mandir has been constructed in the traditional Nagara style of temple architecture

[News](#) ▾[Business](#) ▾[Tech & Industry](#) ▾[Entertainment](#) ▾[Education](#) ▾[Health](#) ▾

The construction of the Shree Ram Mandir saw TCE implementing innovative engineering solutions, including:

1. **Utilising Advanced 3D Structural Analysis:** The Mandir underwent a rigorous 3-D Finite Element Method (FEM) Static and Dynamic Structural analysis, akin to what is employed for nuclear plants. This analysis was conducted to ensure the long-term structural integrity of the Monument, considering various design loads, including seismic forces, over a staggering return period of 2,475 years.
2. **Unprecedented Foundation Innovation:** TCE came on board while the foundation design was already underway. During the initial pile work for the foundation, unforeseen issues emerged, necessitating a thorough review. TCE's team of experts, in collaboration with a panel of distinguished engineers, conducted an extensive assessment of the design, revealing vulnerabilities, particularly in relation to seismic forces and limited lateral load capacity.

In response, TCE proposed an innovative solution – the use of roller-compacted concrete (RCC) as an engineered fill. This innovative concept, a pioneering endeavour worldwide, received approval from experts, substantiated by settlement analysis confirming its feasibility. A remarkable 130,042 cubic meters of roller-compact concrete was employed as an innovative Engineered Fill, reaching heights of 12 to 14 meters from the Raft's bottom. This pioneering approach not only ensured the structural integrity of the temple's foundation but also addressed the unique geological challenges presented by the site. Furthermore, the excavation required for the engineered fill provided an opportunity to unearth cultural debris discovered at depths of 18-20 meters, adding a significant archaeological dimension to the project.

3. **Innovative Raft Foundation Solution:** The construction of the raft involved the use of 9,432 cubic meters of concrete. A comprehensive thermal analysis was carried out to determine the concrete's properties before and after pouring. Based on this analysis, the dimensions of the pour were determined as 9 meters by 9 meters with a thickness of 1.5 meters in square sections. To maintain the concrete temperature below 20 degrees Celsius, a chiller plant was installed to lower the water temperature by 7 to 10 degrees Celsius. Additionally, crushed ice was employed to reduce the concrete temperature further.

4. **Reimagining the Plinth Foundation:** Originally planned with sedimentary rock consisting of

---

feet, were employed, featuring an essential interlocking arrangement, holes, and keys. Vacuum lifters were introduced for efficient, effective, and safe handling.

5. **Employing 4D Modelling for Project Management:** To ensure the project adhered to its timelines, TCE employed 4D Modelling. This advanced modelling technique, which integrates the dimension of time into traditional 3D models, offers a dynamic and comprehensive tool for effectively overseeing complex projects and offers a real-time status in relation to the planned schedule. This approach facilitated a better understanding and monitoring of project progress.

6. **Innovative Solution for Kuber Tila:** The natural tilla had slopes susceptible to instability and erosion, particularly on its western, southwestern, and southern sides. Geotechnical investigations revealed collapsible soil at the surface and soil fill of loose silt and sand in certain areas, further complicating the stability issue. To overcome these challenges, TCE explored various solutions, ultimately deciding on a mechanically stabilised buttressed soil mass encircling the tilla area. This innovative approach eliminated the risk of slope failure. Among the options considered, TCE recommended the use of geo-cells filled with soil and gravel. This flexible system not only stabilised the slope but also provided an aesthetically pleasing solution, matching the architectural design requirements. The solution allowed water seepage without developing pore water pressure and facilitated vegetation growth for added stability and visual appeal.

7. **Landscaping of the Project:** TCE played a crucial role in the landscaping of the temple complex. The first phase of the project involved the development of approximately 40,000 square meters (nearly 10 acres) of hardscape, which included walkways and other solid surface areas designed for heavy foot traffic and aesthetic appeal. The softscape of the temple complex was also meticulously planned, covering a substantial area of 16.85 acres in the first phase. The landscape design beautifully accommodated the Jatayu sculpture and the existing hilltop Shiv temple both seamlessly integrated into the overall design.

8. **Pilgrim Facilitation Centre and Allied Services:** As the principal consultant for design review, engineering, and project management, TCE is instrumental in shaping these auxiliary structures, ensuring they meet the needs of the visitors while enhancing the overall functionality of the temple complex. Key elements in addition to the pilgrim facilitation centre are a dedicated Fire Post, Water Treatment Plants, medical facilities, RO systems, an exclusive VIP Lounge, Electrical Substation Buildings, STPs and Public conveniences, comprehensive security measures such as a Command control centre, Baggage scanning and Frisking areas, a Fire hydrant system, an intelligent Building

9. The Parkota: TCE is also the design review, engineering and project management consultant for the Parkota. This 732-meter-long square Parkota connects to the temple with an east/west length of 165 meters and a north/south length of 201 meters. It is estimated that 7.91 lakh cubic feet of Bansi Paharpur Red Sandstone will be utilised when the full Parkota is completed. The entire pathway is designed to be 14 feet wide and features six Mandirs along its periphery.

The main monument boasts impressive dimensions of 108 meters in length 75 meters in width, and reaches a towering height of 49 meters. It stands supported by a remarkable assembly of 392 pillars, each boasting a floor-to-floor height of 19 feet and 11 inches. The superstructure elements, including columns, pillars, walls, beams, slabs, mandaps, and more, are meticulously crafted from Bansi Paharpur sandstone and intricately interconnected with Copper Pins and Clamps to ensure structural integrity.

Within the monument's grandeur, you will find a total of 42 doors, meticulously fashioned from Maharashtra teakwood. Among these, 14 doors on the ground floor will be adorned with gold plating, adding a touch of opulence to the temple's design. To further enhance the construction, specialised 20 MPa bricks have been utilised in the lower plinth and for packing the Bansi Paharpur columns, reflecting a commitment to both durability and precision in this remarkable architectural endeavour.

Mr. Amit Sharma, MD & CEO of Tata Consulting Engineers, said: "TCE has been at the forefront of this project, contributing significantly to its design, planning, and successful execution. The construction of the Shri Ram Temple in Ayodhya is a remarkable achievement and a testament to our unwavering dedication, hard work, and commitment. I commend the entire engineering team in Ayodhya for their focus and determination that has led TCE to deliver innovative engineering solutions. It has been an honour for TCE to have contributed its extensive expertise in structural engineering, architectural design, and project management to create this masterpiece of engineering excellence."

The temple is expected to attract devotees and tourists from all corners of the globe, promoting religious tourism and boosting the local economy.

Shri Champat Rai, General Secretary of Shri Ram Janmabhoomi Teerth Kshetra, acknowledged TCE's contribution and said, "Tata Consulting Engineers is a renowned engineering consulting firm



Beyond this monumental endeavour, the company is actively involved in spearheading numerous prestigious projects across India. TCE's portfolio encompasses diverse initiatives, such as the development of high-speed rail networks, the transformation of over 15 smart cities, the enhancement of 50+ AMRUT cities, innovative water management initiatives, and invaluable contributions to India's esteemed nuclear and space programs, to name just a few.

Tata Consulting Engineers continues to exemplify innovation, excellence, and a deep commitment to shaping a brighter future for the nation through its pioneering engineering solutions.



NS

---

## Leave a Reply

Your email address will not be published. Required fields are marked \*

**Comment \***

**Name \***

